Product Specificationand Maintenance Guide



PSMG-XPIND30000			
Date	October 2021		
Code	XPIND30000		
Description	XPRESS Industrial Tank 30000L		

Specifications

Capacity (L)	Diameter (mm)	Height (mm)	Outlets	Manhole Dia (mm)
30000	3660	3150	2x 50mm	600

Standard Complies with:

- AS/NZS 4020: Products in contact with drinking water
- AS/NZS 2070 (INT): Plastics material for food contact use

• Potable Water Storage

- Retention/Detention Stormwater Management
- Industrial Applications

Statement

In line with today's focus on Ecologically Sustained Development, Green Building Initiatives and 5 Star Ratings, Promax is committed to supplying quality Liquid Storage and Handling Solutions

Promax Plastics confirms that if these tanks are installed according to Good Management practices set out in the Promax Installation Guides, they will perform as stated throughout their intended life.

Maintenance

Description	Action	Frequency
Tank Stability	Tank must remain level, foundation must not become eroded	Monthly
Tank Lid	Remains securely fitted	Bi-Monthly
Inlet/Outlet Fitting	Remains securely fitted with no leakage	Bi-Monthly
Pump	Check Pump, if fitted, for inlet screen blockages	Bi-Monthly
Sediment Build Up	Remains lower than base outlet - if outlet flow becomes restricted remove sediment with vacuum truck. Re-attach tank lid securely.	Half yearly or as necessary

Please note: Entry into this tank is at owners risk.

Authorised By:

Promax Engineered Plastics Limited PO Box 749, Kerikeri 0245, New Zealand



Product Specification and Maintenance Guide



Responsibility	The owner/s are responsible for maintenance of the tank.
Post Storm Inspection	Following a storm event it is recommended that a full tank inspection is carried out, please refer the maintenance section for guidelines on this.
Debris removal programme	If debris is identified in either a regular maintenance check or post storm inspection it is recommended that this is removed by a professional stormwater maintenance provider.

Maintenance records

Date	Comments	Completed

